

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20592-00-00
Spot: E2E2W2SE Sec/Twnshp/Rge: 7-24S-38W
1320 feet from S Section Line, 1442 feet from E Section Line
Lease Name: ROTH Well #: 1-2
County: KEARNY Total Vertical Depth: 2950 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2718		WITH 2 SX CMT
SURF	8.625	523		WITH 300 SX CMT
PROD	5.5	2950	0	WITH 650 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/14/2011 3:30 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: OZZIE Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: CIBP @ 2715' & 2 SX CMT. FILL 5 1/2" FROM 1980' TO SURFACE WITH CMT. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2011 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2718' WITH 2 SX CMT. ADD FLUID BACK TO 2000' (9 BBLS). FILL 5 1/2" CASING WITH CMT FROM 2000' TO 0' USING 220 SX CMT. PRESSURE TO 500#. HOLDING. BLEED OFF AIR & TOP OFF WITH 10 SX CMT. PUMP 30 SX CMT DOWN ANNULUS TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2766	2834		COUNCIL GROVE

RECEIVED
AUG 08 2011

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY COPELAND

Plugged through: CSG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED

JUL 28 2011

KCC DODGE CITY

Form 1-2/3