

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01825-00-01
Spot: NWNESW Sec/Twnshp/Rge: 27-28S-7W
1989 feet from S Section Line, 3403 feet from E Section Line
Lease Name: ALAMEDA UNIT OWWO Well #: 12-1
County: KINGMAN Total Vertical Depth: 4650 feet

Operator License No.: 3880
Op Name: KC RESOURCES, INC. DBA CRYSTAL R
Address: P. O. BOX 6749
SNOWMASS VILLAGE, CO 81615

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 272 | | 240 sxs |
| PROD | 5.5 | 4429 | | 225 sxs |

Well Type: {EOR} UIC Docket No: E13079.2 Date/Time to Plug: 03/08/2011 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: JIM KRAFT Company: Phone: (620) 388-2356

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/24/2011 10:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:
3/8/11 CASING PARTED AT 727' (RAN VIDEO CAMERA DOWN HOLE) ON VERY LARGE VAC, RAN TUBING INTO 815' - PUMPED 200 SXS OF COMMON CEMENT AND 500 LBS. OF HULLS WITH 3% CC, SHUT VAC OFF. STARTING 3/10/11 TAKING MOST OF FOUR DAYS PUMPED 950 SX OF COMMON CEMENT. 15,000 LBS OF HULLS, 8000 LBS OF SALT MUD. 500 BBLs OF HEAVY SALT WATER MIXED WITH FLOW GEL. ON 3/15/11 TAGGED TOP OF MUD AT 690'. 3/16/11 CIRCULATED TO SURFACE WITH 100 SX OF COMMON CEMENT 3% CC. 3/24/11 CUT HEAD OFF HAD CEMENT TO SURFACE INSIDE AND OUT.

Perfs:

RECEIVED
AUG 10 2011
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, KS -- COMMISSION ORDER TO PLUG: BECAUSE PARTED CASING ON SCREAMING VACUUM DUE FOR MIT.

Plugged through: TBG

District: 02 Signed B. J. Hope (TECHNICIAN)

Form CP-2/3
cc to MK 8/11/11

JK