

18/10-ml.

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21001-00-01
Spot: NESWSESW Sec/Twnshp/Rge: 15-30S-18W
597 feet from S Section Line, 3388 feet from E Section Line
Lease Name: D UNRUH Well #: 1
County: KIOWA Total Vertical Depth: 5802 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4585		WITH 2 SX CMT
CIBP		5005		
SURF	8.625	580		WITH 400 SX CMT
PROD	5.5	5801	726	WITH 400 SX CMT

Well Type: SWD UIC Docket No: D25237.0 Date/Time to Plug: 07/22/2011 2:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: ERIC RICKE Company: OIL PRODUCERS Phone: (316) 215-1357

Proposed Plugging Method: SET CIBP @ 4850' WITH 2 SX CMT. PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 240' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: NONE
Date/Time Plugging Completed: 07/25/2011 10:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SET CIBP @ 4585' WITH 2 SX CMT. COULD NOT GET CIBP ANY LOWER. 1ST PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 610' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 7/25/11: TOPPED OFF WITH 100 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4904	4908		MARMATON

RECEIVED
AUG 10 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY BASIC EBERGY SERVICES.

Plugged through: TBG

District: 01

RECEIVED
AUG - 4 2011
KCC DODGE CITY

Signed Steve Durrant
(TECHNICIAN)

Form CP-2/3
✓
doc to MIC 8/1/11