

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-085-20032-00-00
Spot: NWNENW Sec/Twnshp/Rge: 22-7S-13E
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HLADKY Well #: 4
County: JACKSON Total Vertical Depth: 3420 feet

Operator License No.: 5721
Op Name: GLACIER PETROLEUM CO., INC.
Address: 825 COMMERCIAL ST PO BOX 577
EMPORIA, KS 66801

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	300		
PROD	5.5	3420		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2011 9:00 AM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: MARK LYNCH Company: GLACIER PETROLEUM CO., INC. Phone: (620) 342-1148

Proposed Plugging Method: SET WIRELINE BP @ 3250 FT W/ 2SX CEMENT ON TOP, PART AND PULL CASING (APPROX. 1200 FT, SPOT 25 SX PLUG AT PART, CIRC 100 FT PLUG FROM 350 FT TO 250 FT, FILL SURFACE W/ MUD FROM 250 FT TO 60 FT., CEMENT INSIDE SURFAVE FROM 60 FT TO GROUND LEVEL.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 05/09/2011 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

SET BRIDGE PLUG AT 2720' AND PUMPED 2 SACKS OF CEMENT ON TOP OF BRIDGE PLUG. PERFORATED THE 5.5" CASING AT 1245' AND PARTED THE 5.5" CASING. RETRIEVED 1245' OF 5.5" CASING. RAN 2 3/8" TUBING TO 1245' AND PUMPED 20 SACKS OF CEMENT. PULLED THE 2 3/8" TUBING TO 350' AND PUMPED 35 SACKS OF CEMENT. PULLED 2 3/8" TUBING TO 50' AND PUMPED 20 SACKS OF CEMENT TO THE SURFACE.

RECEIVED
JUL 13 2011 TCH
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

RECEIVED
JUL 20 2011
KCC WICHITA
Form CP-2/3