

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-07057-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 36-20S-14W  
1650 feet from S Section Line, 330 feet from W Section Line  
Lease Name: WRIGHT Well #: 6  
County: BARTON Total Vertical Depth: 3542 feet

Operator License No.: 33725  
Op Name: FOUNDATION ENERGY MANAGEMEN  
Address: 14800 LANDMARK BLVD STE 220  
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	377	0	w/unknown sxs cmt
PROD	5.5	3541	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2011 9:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: KENT STRUBE Company: FOURNDATION ENERGY MANAG Phone: (620) 786-4161

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.  
Perfed at 1600' - 750' - 360'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/14/2011 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3000' - pumped 50 sxs cement with 200# hulls.  
Perfed at 1600' - 750' - 360'.  
Ran tubing to 1000' - well started flowing - pumped 10 sxs gel - well quit flowing.  
Ran tubing to 1600' - pumped 100 sxs cement with 250# hulls.  
Pulled tubing to 750' - pumped 250 sxs cement with 50# hulls - circulated cement out casing and surface pipe.  
Pulled tubing and topped off with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3489	3533		

RECEIVED  
JUL 22 2011  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM