

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-21012-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 34-12S-32W
478 feet from N Section Line, 357 feet from E Section Line
Lease Name: DALE Well #: 2-34
County: LOGAN Total Vertical Depth: 4730 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		165 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/03/2011 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: TONY MARTIN Company: GRAND MESA OPERATING COMP Phone: (316) 265-3000

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 07/03/2011 5:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 2520' w/25 sxs.
2nd. Plug at 1540' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED
JUL 25 2011
KCC WICHITA

District: 04

Signed Richard Williams
(TECHNICIAN)

CM