

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22481-00-00  
Spot: SWSW Sec/Twnshp/Rge: 28-19S-6W  
688 feet from S Section Line, 4640 feet from E Section Line  
Lease Name: FRANCISCO Well #: 1  
County: RICE Total Vertical Depth: 3300 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237		180 SX CMT.
T1	2.375	3244		
PROD	5.5	3348	1410	165 SX CMT.

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2011 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 07/11/2011 11:45 AM

KCC Agent: SHANE JONES

Actual Plugging Report:

7/8/11 KELSO'S DROPPED SAND AND TAGGED IT @ 3160' CAPPED WITH 5/SX. THEY PULLED STRETCH IN 5 1/2". THEY RIPPED @ 1410' AND PULLED CASING TO 920' 7/11/11 COPELAND OUT AND TIED ON TO CASING. THEY SPOTTED A 35 SX HOT PLUG @ 920'. KELSO'S PULLED CASING TO 525'. WAITED HOUR AND WENT BACK DOWN WITH SAND LINE TO TAG PLUG. THEY TAGGED PLUG @ 900'. COPELAND TIED BACK ON AND SPOTTED 35 SX @ 525'. KELSO'S THEN PULLED CASING TO 300'. COPELAND TIED BACK ON AND CIRCULATED CEMENT TO SURFACE. KELSO'S PULLED THE REST OF THE CASING. HOLE STANDING FULL. COPELAND TK #36903. 185 SX 60/40 POS W/4% GEL. 7/12/11 I TAGGED TOP PLUG @ 14' DOWN FROM SURFACE. AMERICAN ENERGIES WILL CUT OFF CASING AND TOP OFF HOLE WITH SACK CEMENT.

Perfs:

Top	Bot	Thru	Comments
3200	3236	CSG	MISSISSIPPIAN
3195	3220	CSG	MISSISSIPPIAN

Remarks: NO TA FILED.

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

JUL 25 2011

Form CP-2/3

KCC WICHITA