

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01473-00-00
Spot: SWSENW Sec/Twnshp/Rge: 26-19S-2W
3146 feet from S Section Line, 3610 feet from E Section Line
Lease Name: WILLIAMS Well #: 3
County: MCPHERSON Total Vertical Depth: 2960 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	161		100 SX CMT
PROD 5		2940		100 S XCMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/05/2011 8:00 AM

Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: IN ACCORDANCE WITH KCC REQUIREMENTS.

Plugging Proposal Received By: JEFF KLOCK

Witness Type: PARTIAL

Date/Time Plugging Completed: 07/05/2011 8:00 AM

KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

Perfs:

*CASING STUCK IN HOLE. THE PERFS WERE SANDED OFF AND CAPPED W/5 SX. TOP PLUG WAS SET AT 450' AND WAS TAGGED AT 415', 90 SX OF CEMENT WERE PUMPED TO SURFACE. 1" TUBING WAS RUN DOWN THE BACKSIDE AND STACKED OUT AT 160'. PULLED UP TO 150' AND PUMPED 80 SXS ON BACKSIDE AND CIRCULATED TO SURFACE. CEMENT IN CASING FELL 3' AND WAS CAPPED. TICKET #37717.

Top	Bot	Thru	Comments
2911	2935	CSG	

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED

Form CP-2/3

JUL 25 2011

KCC WICHITA

JK