

1 090047

175-171-00036-0000

1470

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER ~~15~~ NA
C NW NW, SEC. 12, T 20 S, R 33 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5317

Lease Name Wassinger Well # 1

Operator: Continental Energy
Name & Address: P.O. Box 918
Garden City, KS 67846

County Scott 151.12

Well Total Depth 4650 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Continental Energy License Number 5317-110 - 110

Address P.O. Box 918, Garden City, KS 67846

Company to plug at: Hour: 11:15 a.m. Day: 17 Month: 1 Year: 19 91

Plugging proposal received from Kevin Wiles

(company name) Continental Energy (phone) 316-276-8710

were: 4 1/2" at 2033' w/75 sx cement, 5 1/2" at 4650' w/150 sx cement, Perfs at 4618-23'

1st plug sand back to 4645' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 10 sx gel and 80 sx cement at 1300',

3rd plug pump .50 sx cement at 400',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 17 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4645' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 10 sx gel and 80 sx cement at 1180',

3rd plug pulled to 400', spotted 50 sx cement,

4th plug pulled to 40', spotted 10 sx cement.

Cement circulated.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1210' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (could not observe this plugging.)

DATE 2-11-91
INV. NO. 30650

Signed [Signature] (TECHNICIAN)