

1 051942

7-29

API NUMBER 15- 171-20,489-0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

E/2 NE SE, SEC. 11, T 20 S, R 33 W/E  
1981 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003  
Operator: McCoy Petroleum Corporation  
Name & Address: 3017 N. Cypress  
Wichita, KS 67226-4003

Lease Name Wasinger B Well # 1-11  
County Scott 157.63  
Well Total Depth 4850 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sweetman Drilling, Inc. License Number 5658

Address: 3017 N. Cypress, Wichita, KS 67226-4003

Company to plug at: Hour: \_\_\_\_\_ Day: 29 Month: 7 Year: 1995

Plugging proposal received from Eugene Saloga

(company name) Sweetman Drilling, Inc. (phone) 316-636-2737

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2100-70'

1st plug at 2160' with 50 sx cement, 2nd plug at 1250' with 80 sx cement,

3rd plug at 390' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
Richard Lacey  
AUG 8 1995  
8-7-95  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_

Operations Completed: Hour: 5:35 a.m. Day: 29 Month: 7 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,

2nd plug at 1250' with 80 sx cement,

3rd plug at 390' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not observed, observe this plugging.)

DATE 8-8-95

Signed Richard W. Lacey (TECHNICIAN)

WKS NO. 4325 #

7-29