

1 050743

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,316- 0000
NE, SEC. 8, T. 20 S, R. 33 W/EX

TECHNICIAN'S PLUGGING REPORT

4840 feet from S section line
2200 feet from E section line

Operator License # 5210

Lease Name Keyse Well # 1-8

Operator: Lebsack Oil Production, Inc.
Name & Address P. O. Box 489
Hays, KS 67601

County Scott 154.70
Well Total Depth 4760 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 428

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 11:00 pm Day: 13 Month: January Year: 19 86

Plugging proposal received from Wayne Shively
(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2174-90'
1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 1200' with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:25 am Day: 14 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2190' with 50 sx cement, 2nd plug at 1200' with 80 sx
cement, 3rd plug at 458' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement. 6th plug to circulate rat hole
with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1986
1-16-86
CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED (xxx / did not) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 1-16-86
INV. NO. 12091