

To: 1080152 10-22
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
RECEIVED
KANSAS CORP COMM
TECHNICIAN'S PLUGGING REPORT 10-24-97
1997 OCT 24 A 11:54
Operator License # 4243

API NUMBER 15- 171-20,521-0000
SW SE SE, SEC. 2, T 20 S, R 33 W/E
330 feet from S section line
990 feet from E section line

Operator: Cross Bar Petroleum, Inc.
Name & Address: 7570 W. 21st, Bldg. 1014, Ste. B
Wichita, KS 67205

Lease Name Collingwood Well # 1-2
County Scott 156.00
Well Total Depth 4800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382
Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 12:30 p.m. Day: 22 Month: 10 Year: 19 97

Plugging proposal received from Phil Lloyd

(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2150'
1st plug at 2150' with 50 sx cement, 2nd plug at 1320' with 80 sx cement,
3rd plug at 450' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 2:30 p.m. Day: 22 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2145' with 50 sx cement,
2nd plug at 1400' with 80 sx cement,
3rd plug at 540' with 50 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED
DATE OCT 27 1997
INV. NO. 49335
10-22

Signed Kevin D. Shurtz (TECHNICIAN)