

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20277-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 6-20S-33W
550 feet from S Section Line, 600 feet from E Section Line
Lease/Unit Name: LANG Well Number: 1-6
County: SCOTT Total Vertical Depth: 4794 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION, INC.
Address: BOX 489 1303 MAIN ST.
HAYS, KS 67601

Conductor Pipe: Size feet: #155.81
Surface Casing: Size 8.625 feet: 425 WITH 300 SX CMT
Production: Size 5.5 feet: 4788 WITH 180 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/01/2001 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 4000' & 5 SX CMT. 1ST PLUG AT 1250' WITH 80 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/01/2001 12:30 PM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4788'. PERFS AT 4671-76 & 4699-4701'. SANDED BACK TO 4400'. 1ST PLUG PULLED CASING UP TO 1247' PUMPED 8 SX GEL - 80 SX CMT & DISPLACED WITH 7 SX GEL. 2ND PLUG PULLED CASING UP TO 460' & PUMPED 50 SX CMT. 3RD PLUG PULLED CASING UP TO 40' & PUMPED 10 SX CMT.

INVOICED
DATE 03-08-2001
WEL NO. 2001061463

RECEIVED
STATE CORPORATION COMMISSION

MAR 6 2001
3-6-01
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1610' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Kevin D Strube

(TECHNICIAN)

MAR 02 2001

Form CPX/3