

1 030502

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-171-20,301-0000  
150' North  
C NW NE, SEC. 5, T 20 S, R 33 W/E

4770 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Lease Name Hattendorf Well # B-2

Operator: Lebsack Oil Production, Inc.

County Scott 154.38

Name & Address P. O. Box 489

Well Total Depth 4750 Mississippi feet

Hays, KS 67601

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 407 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KM 67202

Company to plug at: Hour: 5:00 am Day: 3 Month: September Year: 1985

Plugging proposal received from Wayne Shively

(company name) Abercrombie (phone) 316-262-1841

Elevation 2983 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2171-87'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:00 am Day: 3 Month: September Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 2185' with 50 sx cement, 2nd plug at 1285' with 80 sx

cement, 3rd plug at 435' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement,

RECEIVED  
STATE CORPORATION COMMISSION

SEP 6 1985

9-6-85

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton 089722-6

(If additional description is necessary, use BACK of this form.)

INVOICED  
SEP 16 1985

(If additional description is necessary, use BACK of this form.)

Signed Steve Durrant  
(TECHNICIAN)

*Handwritten signature/initials*

DATE \_\_\_\_\_  
INV. NO. 10011