

1090336

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,292-0000

C NW SE, SEC. 5, T 20 S, R 33 W/EX

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Lease Name Hattendorf Well # 4

Operator: Lebsack Oil Production, Inc.

County Scott 38

Name & Address Box 489

Well Total Depth 4750 (Mississippi) 154 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 428

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 10:00 pm Day: 13 Month: May Year: 19 85

Plugging proposal received from Wayne Shively

(company name) Abercrombie (phone) 316-262-1841

Elevation 2985

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2173-99'

1st plug at 2220' with 50 sx cement 2nd plug at 1590' with 50 sx cement

3rd plug at 750' with 50 sx cement 4th plug at 450' with 40 sx cement

5th plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

Balance plugs with mud
7th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 am Day: 14 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement, 2nd plug at 1590' with 50
sx cement, 3rd plug at 750' with 50 sx cement, 4th plug at 450' with 40 sx cement

5th & 6th plugs- solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, balance plugs with mud. 7th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1985
5-21-85

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton # 089209

(if additional description is necessary, use BACK of CONSERVATION DIVISION
Wichita, Kansas

INVOICED (did not) observe this plugging.

Signed Robert B. Tarbutton
(TECHNICIAN)

DATE 5-21-85

INV. NO. 8209 5-14