

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-073-23116-00-01  
Spot: NENWSW Sec/Twnshp/Rge: 34-22S-10E  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: UNDERWOOD Well #: SWI-1  
County: GREENWOOD Total Vertical Depth: 2210 feet

Operator License No.: 5892  
Op Name: BERENTZ DRILLING CO., INC.  
Address: PO BOX 782228  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	122		80 SX
PROD	5.5	2209		125 SX

Well Type: EOR UIC Docket No: E24016.1 Date/Time to Plug: 06/02/2011 8:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: BILL SOULE Company: Phone: (620) 583-5389

Proposed Plugging Method: 50' cement plug @ 2080' 15 sxs cement 50' cement plug @ 963' 25 sxs cement, 155' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 06/02/2011 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2080' pumped 15 sxs cement, pulled tubing to 963' pumped 25 sxs cement, pulled tubing to 155', pumped 169 sxs cement to surface.gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2134	2153		

RECEIVED

JUN 13 2011 MH

KCC Granute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed Michael Heffern  
(TECHNICIAN)

RECEIVED

JUN 15 2011

KCC WICHITA

Form CP-2/3