

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21912-00-00
Spot: NESWSEW Sec/Twnshp/Rge: 33-14S-31W
1985 feet from N Section Line, 1785 feet from W Section Line
Lease Name: THIES RANCH Well #: 2-33
County: GOVE Total Vertical Depth: 4450 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	249		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/31/2011 12:00 AM
Plug Co. License No.: 34432 Plug Co. Name: FALCON DRILLING, LLC
Proposal Rcvd. from: PORSIRIO Company: LARIO OIL & GAS COMPANY Phone: (316) 265-5611

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN Witness Type: NONE
Date/Time Plugging Completed: 05/31/2011 4:15 AM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 2170' w/25 sxs.
2nd. Plug at 1170' w/100 sxs.
3rd. Plug at 310' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.


Perfs:

Remarks: CONSOLIDATED ACID AND CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
JUN 09 2011

KCC WICHITA

Form CP-2/3

JUN 07 2011