

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20802-00-02  
Spot: W2NW Sec/Twnshp/Rge: 10-25S-18W  
2979 feet from S Section Line, 4542 feet from E Section Line  
Lease Name: STRAWN Well #: 1-10  
County: EDWARDS Total Vertical Depth: 4551 feet

Operator License No.: 9971  
Op Name: KODIAK PETROLEUM, INC.  
Address: PO BOX 4677  
ENGLEWOOD, CO 80155

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	618		
PROD	4.5	4543	2100	WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2011 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 4350' WITH 4 SX CMT. PLUG AT 1240' WITH 15 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE  
Date/Time Plugging Completed: 07/22/2011 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND TO 4340' WITH 4 SX CMT. 1ST PLUG AT 1250' WITH 15 SX GEL & 50 SX CMT.  
2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4400	4410		MARMATON

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY ALLIED

Plugged through: TBG

District: 01

Signed

Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED

JUL 26 2011

KCC DODGE CITY

RECEIVED  
AUG 01 2011  
KCC WICHITA

Form CR-2