

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33392
Name: Keith F. Walker Oil & Gas Co., LLC
Address 1: P.O. Box 1725
Address 2: _____
City: Ardmore State: OK Zip: 73402 + 6305
Contact Person: Danyelle Barksdale
Phone: (405) 701-0676
Type of Well: (Check one) Oil Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No

API No. 15 - 025-21491-00-00
Spot Description: _____
NW - NE - SW - SW Sec. 7 Twp. 33 S. R. 25 East West
4,000-1031 Feet from North / South Line of Section
780-848 Feet from East / West Line of Section
GPS - KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Clark
Lease Name: Idun Well #: 7-1
Date Well Completed: 2/23/2010
The plugging proposal was approved on: 7/22/2011 (Date)
by: Eric McLaren (KCC District Agent's Name)

Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 4469 Bottom: 4476 T.D. _____
Pawnee Depth to Top: 5130 Bottom: 5136 T.D. _____
Chester Depth to Top: 5442 Bottom: 5447 T.D. _____
Viola 6720 6710

Plugging Commenced: 7/20/2011
Plugging Completed: 7/22/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		0-94	20"	94	0
		0-1171	8 5/8"	1171	0
		0-7059	5 1/2"	7059	1691

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 40 bbls mud down 5 1/2 casing. Set CIBP @ 4411'. Pumped 10 sacks of cement on top. Loaded casing with mud. Cut 5 1/2" casing @ 2115', no success. Cut casing @ 1691'. Laid down same. TIH with tubing to 1200'. Pumped mud and 300 lbs. of cottonseed hulls. Pumped 75 sacks of cement. TOH to 600'. Pumped 50 sacks of cement. TOH to 60'. Pumped 20 sacks of cement.

Plugging Contractor License #: 33311 Name: Phil Dollaar Oilfield Sevices, Inc.
Address 1: P.O. Box 744 Address 2: _____
City: Perryton State: TX Zip: 79070 + _____
Phone: (806) 435-3373
Name of Party Responsible for Plugging Fees: Keith F. Walker Oil + Gas Co., LLC
State of Oklahoma County, Cleveland, ss.
Danyelle Barksdale Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Danyelle Barksdale

RECEIVED

AUG 15 2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA



Phone: 405.701.0676

Fax: 405.310.5074

Keith F. Walker
Oil & Gas Company, LLC

August 11, 2011

Kansas Corporation Commission
Conservation Division- Oil & Gas
130 S. Market, Room 2078
Wichita, Kansas 67020

Re: Well Plugging Records

To Whom It May Concern:

Please find enclosed (2) two Well Plugging Records (Form CP-4).

- (1) Idun 7 #1 in Sec. 7-33S-25W, Clark Co.
- (2) Freyja 18 #1 in Sec. 18-33S-25W, Clark Co.

If you should require additional information or have any questions, please contact me at 405.701.0676 or dbarksdale@kfw.gs.

Sincerely,
KEITH F. WALKER OIL & GAS COMPANY, LLC

Danyelle Barksdale

~~Danyelle Barksdale~~
Engineer Tech

103 West Boyd
Norman, OK 73069

RECEIVED
AUG 15 2011
KCC WICHITA