

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-21,678-000

LEASE NAME Kinderknect B.

WELL NUMBER 8

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 8 TWP. 14 RGE. 19 (X) or (W)

COUNTY Ellis

Date Well Completed 5/2/79

Plugging Commenced 8/19/87

Plugging Completed 8/19/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR LASMO Energy Corporation

ADDRESS P.O. Box 1365, Great Bend, Kansas 67530

PHONE# (316) 792-2585 OPERATORS LICENSE NO. 4678

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3849 Bottom 3861 T.D. 3861

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	261'	None
				4-1/2"	3849'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pumped 120 sacks econo-lite cement with 4 sacks hulls down 4-1/2"
production casing. Pumped 2 sacks econo-lite cement down annulus. 800#
OK, 1700# Maximum, 1000# shut in pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan Services License No. N/A

Address 925 Patton Road, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Claude Blakesley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Claude Blakesley

(Address) P.O. Box 1365, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 87



My Commission Expires: 03-05-88

Notary Public
STATE CORPORATION COMMISSION

SEP 9 1987 Form CP-4
9-9-87 Revised 08-84
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG


API No. 15 — 051 — 21,678
 County Number

S. 8 T. 14S R. 19W E W

Loc. SW/4 NW/4 NE/4

County Ellis

640 Acres
N



Elev.: Gr. 2216

DF 2218 KB 2,221'

Operator Frontier Oil Company

Address 1720 KSB&T Building, Wichita, Kansas 67202

Well No. 8 Loose Name Kinderknecht "B"

Footage Location 990 FNL 2310 FEL
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Red Tiger Drilling Company Geologist Richard Parker

Spud Date April 19, 1979 Total Depth 3,861' P.B.T.D.

Date Completed May 2, 1979 Oil Purchaser NCRA

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	260.78'	Common	165	2% Gel, 3% C.C.
Production	7 7/8"	4 1/2"	9.5#	3,849'	Common	750	10% Salt, 6% Gel 4% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
					Open Hole

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	3857	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gal 15% INS acid	3849-3861

RECEIVED
STATE CORPORATION COMMISSION

INITIAL PRODUCTION

JUL 1 1987

Date of first production 8-7-79	Producing method (flowing, pumping, gas lift, etc.) Pump	CONSERVATION DIVISION Wichita, Kansas
RATE OF PRODUCTION PER 24 HOURS	Oil 25 bbls. Gas 0 MCF Water 0 bbls.	CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s) 3849-61	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2201. Confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.