

API NUMBER 15-051-21,641-0000

LEASE NAME Kinderknect B

WELL NUMBER 7

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

3630 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 8 TWP. 14 RGE. 19 ~~XX~~ or (W)

COUNTY Ellis

Date Well Completed 2/28/79

Plugging Commenced 8/19/87

Plugging Completed 8/19/87

LEASE OPERATOR LASMO Energy Corporation

ADDRESS P.O. Box 1365, Great Bend, Kansas 67530

PHONE# (316) 792-2585 OPERATORS LICENSE NO. 4678

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3846 Bottom 3854 T.D. 3854

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	269'	None
				4-1/2"	3848'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 120 sacks econo-lite cement with 3 1/2 sacks hulls down 4-1/2"
production casing. 1500 lbs. maximum pressure. 1200# Shut In Pressure.
Annulus OK.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan Services License No. N/A

Address 925 Patton Road, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Claude Blakesley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Claude Blakesley

(Address) P.O. Box 1365, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 87



Kathy A. Hetrick
 Notary Public
 STATE CORPORATION COMMISSION

My Commission Expires: 03-05-88

15-051-21641-0000

DRILLERS LOG

No. 7 Kinderknecht "B"

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 269.03' w/165 sx cement	CONTRACTOR:	Red Tiger Drilling Company	NW/4 SW/4 NE/4 Sec. 8-T14S-R19W Ellis County, Kansas
4 1/2" @ 3,848' w/200 sx cement	COMMENCED:	February 17, 1979	
TOTAL DEPTH: 3,854'	COMPLETED:	February 28, 1979	ELEVATION: 2,223' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Rock & Surface Soil	0	37	
Shale	37	830	
Red Bed	830	934	
Sand	934	1187	
Shale, Salt & Red Bed	1187	1440	
Shale & Red Bed	1440	1491	
Anhydrite	1491	1539	
Shale	1539	1640	
Shale w/Lime	1640	2245	
Lime w/Shale	2245	2455	
Lime & Shale	2455	2670	
Lime w/Shale	2670	2885	
Lime	2885	3200	
Lime & Shale	3200	3234	
Lime	3234	3790	
Lime & Shale	3790	3825	
Lime	3825	3846	
Arbuckle	3846	3854	
RTD		3854	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1987

Subscribed and sworn to before me this 6th day of March, 1979.

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Notary Public