

15-155-20942-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Reno SEC. 22 TWP. 23 RGE. 5 E (W)
 Location as in quarters or footage from lines:
660 ft from NL; 331 ft from E Line

Lease Owner Cliff Whited
 Lease Name Whited Well No. 1
 Office Address 1010 S. Kansas, Liberal, KS 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry (C)(L)
 Date Well Completed 9-3-83
 Application for plugging filed 9-1-83; Verbal with Ron Wilson
 Plugging commenced 9-2-83
 Plugging completed 9-2-83
 Reason for abandonment of well or producing formation Dry

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes; 1030 pm 9-1-83

Name of Conservation Agent who supervised plugging of this well Steve Van Gieson
 Producing formation None Depth to top _____ bottom _____ T.D. 4050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
thru B/ANH.	salt & lime	surf	737'	8 5/8	727'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. 45 Vis mud from 4050 to surface

- pumped 25 sks 50/50 4% Gel 3%CC @ 800'
- pumped 25 sks 50/50-4% Gel 4% CC @ 735'
- pumped 35 sks 50/50 4% Gel 4% CC @ 715'
- pumped 215 sks 50/50 4% Gel Circ cement to surface
- pumped 10 sks Rat hole
- pumped 10 sks Mouse hole


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wheatstate Drilling Company & Allied Cementing Company

STATE OF Kansas COUNTY OF Reno, ss.
 _____ (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]
 (Address) _____

SUBSCRIBED AND SWORN TO before me this 26 day of Sept, 19 83



My Commission expires _____

[Signature]
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION

OCT 3 1983

CONSERVATION DIVISION
 Wichita, Kansas