

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9292
Name: Scheck Oil Operations
Address 1: 211 S. Front
Address 2: _____
City: Russell State: KS Zip: 67665 + _____
Contact Person: Tim Scheck
Phone: (785) 483-4096
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 159-01958-00-00
Spot Description: _____
NE SE NW _____ Sec. 36 Twp. 18 S. R. 8 East West
990 3608 Feet from North / South Line of Section
330 2978 Feet from East / West Line of Section
GPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rice
Lease Name: R J Warner A Well #: 4
Date Well Completed: 10-26-41
The plugging proposal was approved on: 6-16-11 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 7-19-11
Plugging Completed: 7-20-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	10 3/4"	204'	Left in the hole
		Production	6"	3204'	Left in the hole

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug 3153' mixed 50 sacks of cement, displaced with 16 bbls fresh water. 2nd plug 1075' mixed 50 sacks of cement and displaced 4 bbls off fresh water. 3rd plug 725' mixed 50 sacks of cement and displaced 2bbls of fresh water. 4th plug 250' circulated cement to surface with 125 sacks.

Plugging Contractor License #: 33369 Name: Xtreme Well Service
Address 1: P.O. Box 192 Address 2: _____
City: Russell State: KS Zip: 67665 + _____
Phone: (785) 483-1924
Name of Party Responsible for Plugging Fees: Scheck Oil Operations
State of Kansas County: Russell, ss.
TIMOTHY F. SCHECK Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Timothy F. Scheck

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
AUG 31 2011
KCC WICHITA