

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 8210
Name: Edward E Birk
Address 1: 302 South 16th
Address 2: _____
City: Burlington State: Ks Zip: 66839 + _____
Contact Person: Edward E Birk
Phone: (620) 364-1311 - office
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Squirrel - Dry Depth to Top: 992 Bottom: 997 T.D. 1362
Mississippi - Dry Depth to Top: 1316 Bottom: 1362 T.D. 1362
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 031-22980-00-00
Spot Description: _____
NW -SW- SW- NW Sec. 30 Twp. 22 S. R. 17 East West
3,135 Feet from North / South Line of Section
5,115 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Coffey
Lease Name: Bill Parmely Well #: 2
Date Well Completed: 08/05/2011
The plugging proposal was approved on: 08/05/2011 (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 08/05/2011
Plugging Completed: 08/05/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Sandstone/gravel	water	Surface	7"	40'	
Squirrel Sand	dry				
Mississippian	dry				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Connect to drill pipe. Set 50' plug at TD depth of 1362' using 15 sx cement. Mix and pump 2 sx gel. Pull out to base of KC at 615' and set 50' plug using 15 sx cement. Mix and pump 2 sx gel. Pull out to depth of 250'. Set solid plug 250' to surface using 70 sx cement.

RECEIVED
SEP 01 2011

Plugging Contractor License #: 8210 Name: Edward E Birk
Address 1: 302 South 16th Address 2: _____
City: Burlington State: Ks Zip: 66839 + _____
Phone: (620) 364-1311 - office
Name of Party Responsible for Plugging Fees: Edward E Birk
State of Kansas County, Coffey, ss.
Laura C Birk
(Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Laura C Birk

AL