

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5135
 Name: John O. Farmer, Inc.
 Address 1: P.O. Box 352
 Address 2: _____
 City: Russell State: KS Zip: 67665 + 0 3 5 2
 Contact Person: Marge Schulte
 Phone: (785) 483-3145, Ext. 214
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
L/KC Depth to Top: 3175' Bottom: 3511' T.D. _____
Arbuckle Depth to Top: 3512 Bottom: 3515' T.D. _____
 _____ Depth to Top: _____ Bottom: Rotary T.D. 3515'

API No. 15 - 163-02,355•00•00
 Spot Description: _____
SE NE SE Sec. 31 Twp. 10 S. R. 17 East West
1,650 Feet from North / South Line of Section
330 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Rooks
 Lease Name: Ridler "G" Well #: 1
 Date Well Completed: December, 1955
 The plugging proposal was approved on: prior to plugging (Date)
 by: District #4 (KCC District Agent's Name)
 Plugging Commenced: 3:00 P.M., 8-9-11
 Plugging Completed: 3:30 P.M., 8-9-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
L/KC (perforated 3265-3361')	oil & water	surface	8-5/8"	1243'	-0-
Arbuckle (open hole 3514-3515')	oil & water	production	5-1/2"	3514'	-0-
					RECEIVED

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

The casing was perforated prior to plugging: 2 holes @ 1200'

2/3/8 Tubing @ 3318'. Spotted 16 sks. gel & 50 sks. cement w/200# hulls. Pulled up to 1650' & circulated cement to surface w/185 sks. & 300# hulls. Pulled tubing & hooked up to 5-1/2" casing; mixed 50 sks. @ 700# maximum PSI - shut in. Hooked up to annulus & mixed 35 sks. @ 700# maximum PSI - shut in.

SEP 02 2011
9-2-11
KCC WICHITA

Plugging Contractor License #: 99996 Name: Allied Cementing Company, LLC.
 Address 1: P.O. Box 31 Address 2: _____
 City: Russell State: Kansas Zip: 67665 + 0 0 3 2
 Phone: (785) 483-2025

Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.
 State of Kansas County, Russell, ss.
John O. Farmer III, President of John O. Farmer, Inc. Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: John O. Farmer III 8-31-11

DR

STERLING DRILLING CO.

AFE FILE

STERLING, KANSAS

WELL LOG-----

-----ETTA RIDLER "G" #1

Location: SE NE SE, Section 31-10S-17W,
Rooks County, Kansas

OWNER: Tennessee Gas Transmission Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 10-21-55 (w.r.)
COMPLETED: 11-3-55 (w.r.)

COPY

TOTAL DEPTH: 3515'

LOG

0-350	Shale & Shells	
350-665	Shale	
665-1065	Sand & Shale	
1065-1220	Red Bed, Shale, & Sand	
1220-1243	Limestone	
1243-1600	Red Bed & Shale	
1600-1910	Shale & Shells	
1910-2775	Shale & Limestone	
2775-3160	Limestone	
3160-3176	Limestone & Shale	
3176-3215	Lansing, K.C. Limestone	
3215-3430	Limestone	
3430-3485	Limestone & Chert	
3485-3515	Sand & Limestone	T.D.

CASING RECORD

Ran 1243' of 8-5/8" casing set with 600 sacks cement.

Set 5-1/2" casing at 3514' with 250 sacks cement.

*Change file
cel 1-340-proel
1-340-acatg
1-Dev-10w
1-Wichita*

ALLIED CEMENTING CO., LLC. 038139

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell Ks.

DATE <u>8-9-2011</u>	SEC. <u>31</u>	TWP. <u>10</u>	RANGE <u>17</u>	CALLED OUT	ON LOCATION	JOB START <u>3:00 pm</u>	JOB FINISH <u>3:30 pm</u>
LEASE <u>Ridler</u>	WELL # <u>G #1</u>	LOCATION <u>Plainville Ks, S.S 1 1/2 E</u>		COUNTY <u>Rock's</u>	STATE <u>KANSAS</u>		
OLD OR NEW (Circle one)		<u>IS 1 E+S INTO</u>					

COPY

CONTRACTOR POE Well Service
 TYPE OF JOB PLUG ABANDONED Well
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2 DEPTH _____
 TUBING SIZE 2 3/8 DEPTH _____
 DRILL PIPE 6 5/8 SURFACE DEPTH 1243'
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. 3380 from Plug
 PERFS. @ 3265-3361
 DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED 290 60 SX 40 4% GEL
16 SX GEL on Side
500# HULLS on Side

COMMON	<u>174 SK</u>	@ <u>16.25</u>	<u>2827.50</u>
POZMIX	<u>116 SK</u>	@ <u>8.50</u>	<u>986.00</u>
GEL	<u>30 SK</u>	@ <u>21.25</u>	<u>637.50</u>
CHLORIDE		@	
ASC		@	
Hull's	<u>5 SK</u>	@ <u>31.85</u>	<u>159.25</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>Glenn</u>
# <u>417</u>	HELPER <u>Woody</u>
BULK TRUCK	
# <u>481</u>	DRIVER <u>Nick</u>
BULK TRUCK	
#	DRIVER

HANDLING 290 TOTAL SK @ 2.25 652.50
 MILEAGE 22 Ten Mile @ 11¢ 242.80
 TOTAL 5964.55

REMARKS:

290 Tubing @ 3318' Spot 16 SX GEL, +
50 SX Cement w/ 200 # HULLS. Pulled up
to 1650, + Circulated Cement to Surface
w/ 185 SX + 300 # HULLS, Pulled Tubing +
Heated up to 535SG w/ Syringe & mixed 30 SX
@ 200 # MAX PER. + Shut in. Heated up to
ANNULUS + mixed 35 SX @ 200 #
MAX PER. + Shut in. JHANK'S

~~_____~~ SERVICE

DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>1250.00</u>
EXTRA FOOTAGE	@	
MILEAGE HV MT 22x2	@ <u>7.00</u>	<u>308.00</u>
MANIFOLD	@	
LV MT 22x2	@ <u>4.00</u>	<u>176.00</u>

~~_____~~ TOTAL 1734.00

~~_____~~ PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

TOTAL _____

SALES TAX (If Any) _____
 TOTAL CHARGES 7698.55
 DISCOUNT 1895.45 IF PAID IN 30 DAYS 20/50

~~_____~~ 5803.10

CHARGE TO: John R Farmer Oil Co.
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____

SIGNATURE _____

Book LESS Miles
6512.75
208 (1802.55)
5210.20

Miles 1185.80
508 (592.90)
592.90

5210.20
592.90
5803.10

REC'D