

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-035-21,078-0000

LEASE NAME Baker

WELL NUMBER #1

960 Ft. from N Section Line

660 Ft. from E Section Line

SEC. 26 TWP. 33 RGE. 5 (E) ~~XXXX~~

COUNTY Cowley

Date Well Completed \_\_\_\_\_

Plugging Commenced 1-30-96

Plugging Completed 1-31-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Range Oil Company, Inc.

ADDRESS 125 N. Market, #1120 Wichita, Kansas 67202

PHONE# (316) 265-6231 OPERATORS LICENSE NO. 5120

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ if not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3073'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	153'	none
				4 1/2"	3072'	1907'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section.  
Plugged off bottom with sand to 3000', dumped 4 sacks cement. Shot pipe at 1907'. Pulled casing to 250', circulated 133 sacks cement to surface from 250'. (60/40 POZMIX 2% gel).  
Pulled casing. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Range Oil Co., Inc. Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 9th day of February, 1996

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



FEB 12 1996  
CONSERVATION DIVISION  
WICHITA, KS

Form CP  
Revised 05-

DRILLERS LOG

15-035-21078-0000

OPERATOR: Range Oil Company; 240 Page Court; 220 W. Douglas; Wichita, KS 67202

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Baker Well No. 1

Sec. 26 T. 33S R. 5E Spot 300' S of C NE NE

County Cowley State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 153' with 80 Sxs.

Production: 4 1/2" @ 3072' with 75 Sxs.

Type Well: Oil Total Depth: 3073' K.B.

Drilling Commenced: 12-7-76 Drilling Completed 12-12-76

Formation	From	To	Tops
Cellar	0	7	Kansas City 2460
Lime & Shale	7	425	Mississippi 3047
Shale & Lime (Stks)	425	1600	
Shale & Sandy Shale	1600	1800	
Lime	1800	1810	
Shale	1810	1823	
Sand & Shale	1823	1990	
Shale	1990	2460	
Lime	2460	2591	
Shale	2591	2696	
Lime & Shale	2696	2714	
Lime	2714	2798	
Shale	2798	3047	
Lime	3047	3073	

STATE COMMISSION

JAN 15 1977

COMPLETION RECORD

Liner Record: Size From To

Cementing Record: Sacks

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production:

Electric Log Type and Depths Covered