

15-16900852-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
500 INSURANCE BUILDING  
212 NORTH MARKET  
WICHITA 2, KANSAS

Form CP-1

RECEIVED  
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM  
File One Copy

FEB 17 1964  
2-17-64  
CONSERVATION DIVISION  
Wichita, Kansas

Lease Owner Dan Dugan  
(Applicant)  
Address Box 946, Sioux Falls, South Dakota

Lease (Farm Name) SWENSON Well No. 8

Well Location CS/2 SE NE Sec. 25 Twp. 15 Rge. 4 (E) (W) W

County Saline Field Name (If any) \_\_\_\_\_

Total Depth 3402' Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Was well log filed with application? yes If not, explain: \_\_\_\_\_

Date and hour plugging is desired to begin Immediately

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well owner Ace Richardson  
Address Smolan, Kansas

Plugging Contractor Knight Casing Pulling Company License No. 436  
Address Chase, Kansas

Invoice covering assessment for plugging this well should be sent to Dan Dugan  
Address Box 946, Sioux Falls, South Dakota

and payment will be guaranteed by applicant.

Signed: M. J. Toliv  
~~Applicant~~ or Acting Agent

Date: February 15, 1964

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15-169-00852-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

March 11, 1964

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 7 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Dan Dugan

Complete Address: P.O. Box 946, Sioux Falls, South Dakota

Lease Name: Swenson Well No. 8

Location: C S/2 SE NE Sec. 25 Twp. 15 Rge. 4 (E) (W) X

County Saline Total Depth 3402' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3390' and cement with 3 sacks.

Fill hole with mud to 210'. Set rock bridge from 210'

to 200' and cement hole with 20 sacks. Fill hole with mud

to 40'. Set rock bridge from 40' to 30' and cap hole with

10 sacks cement.

Very truly yours,