

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-169-19076-0000

API NUMBER _____

LEASE NAME Benaston

WELL NUMBER 1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 36 TWP. 15 RGE. 4 (X) or (W)

COUNTY Saline

Date Well Completed 8/24/55

Plugging Commenced 1/25/85

Plugging Completed 1/28/85

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 300 Sutton Place, Wichita, Kansas 67202

PHONE# (316) 265 3351 OPERATORS LICENSE NO. 5151

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? 5

Is ACO-1 filed? - - If not, is well log attached? yes

Producing Formation Macquoketa Depth to Top 3417 Bottom 3423 T.D. 3423

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Macquoketa</u>	<u>Oil</u>	<u>3417</u>	<u>3423</u>	<u>8 5/8</u>	<u>319</u>	<u>None</u>
				<u>5 1/2</u>	<u>3417</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sand 3417-3360, Set bridge at 600' fill to surface with redi-mix, fell away, reset plug at 350 fill to surface with redi-mix, held ok. Pump 75 sx 50/50 poz between 8 5/8 and 5 1/2, shut in at 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum/Allied Cementing Co. License No. 5151


Address Gear (see above) Allied Cementing Co., P O Box 31, Russell, KS 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well has filled that the same are true and correct, so help me God.

(Signature) Jim Thatcher

(Address) 300 Sutton Place, Wichita, KS 67202



DESCRIBED AND SWORN TO before me this 22nd day of February, 19 85

Helen L. Coyer
Helen L. Coyer Notary Public

My Commission Expires: April 1, 1986

ROTARY DRILLER'S LOG

E. K. Carey, Contractor
 Box 620
 McPherson, Kansas

Elevation
 1305 K.S.
 1302 D.F.

Langston #1
 C-NW-NW-NW
 Sec. 36-15-48
 Saline County, Kansas

Casing Record
 3 5/8" 310' cemented
 with 250 sacks
 3 1/2" 3477.5' cemented
 with 75 sax

Well Commenced 5-24-51
 Well Completed 6-7-51

Contractor: E. K. Carey, Contractor, (Rlg #2) Box 620, McPherson, Kansas
 Geologist: Donald Roy Smith, 5206 East Central, Wichita, Kansas

Figures Indicate Bottom of Formation K.S.

Rotary Base & Celler	8	Lime	2675
Shale	35	Shale & Lime	2745
Sand	45	Shale * Lime	2807
Shale & Shells	130	Shale & Shells	2900
Shale & Shells	260	Shale	2906
Lime & Shale	319	Lime Miss	2980
Lime	370	Lime	2985
Lime & Shale	630	Lime	3015
Lime & Shale	870	Lime	3054
Lime & Shale	955	Lime	3090
Shale & Shells	1115	Lime	3113
Shale & Shells	1550	Lime	3145
Shale & Shells	1805	Lime	3175
Lime & Shale	1920	Lime	3185
Lime	2055	Shale	3220
Lime & Shale	2065	Shale	3265
Shale & Lime	2170	Shale	3330
Shale & Lime	2240	Hard Lime	3340
Shale	2248	Shale	3360
Lime	2560	Shale	3405
Lime	2445	Shale	3419
Lime	2505	Lime	3423
Lime	2590		

Geologist Tops:

Burgess Sand 2391 (-1593)
 Miss. Lime 2498 (-1593)
 Kinderhook Shale 3135 (-1280)
 Misener Sand 3323 (-2018)

Hunton 3338 (-2027)
 Magnesian Shale 3543 (-2036)
 Magnesian Dolomite 3417 (-2112)
 Total Depth 3423 (-2113)

Drill Stem Test 3418-23
 Open 30 min. recovered 24 stands gas-540' oil 30' water 20 min. BHP
 1210# F.P.P. 2804 out with tester at 6:00 P.M.

The above Rotary Driller's Log is complete and correct to the best of
 my knowledge.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 23 1985

CONSERVATION DIVISION
 Wichita, Kansas

Herbert Hutton
 E. K. CAREY, CONTRACTOR
 By Herbert Hutton, Supt.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 23 1985

CONSERVATION DIVISION
 Wichita, Kansas