

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Saline County, Sec. 35 Twp. 15 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Fender Pipe & Supply, Inc.

Lease Name Liljestrand Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 5-12-66 19

Plugging completed 5-14-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3437 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	340'	None
				4-1/2"	3436'	2983'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3437', sanded to 3425' and dumped 3 sacks of cement @ 3425' with dump bailer. Pulled 4 1/2" casing, set rock bridge from 260' to 250' and dumped 25 sacks of cement @ 250'. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1966
5-24-66
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of May, 1966

My commission expires May 20, 1968
Milton J. Volin Notary Public.

ROTARY DRILLER'S LOG

15-169-00497-00 ⁰²

Derby Oil Co., Operator
Box 1030
Wichita, Kansas

Elevation
1328 K.B.

Liljestrands #1

Casing Record
8 5/8"-340' cemented
with 250 sax

C-SE $\frac{1}{4}$ -SE $\frac{1}{4}$ -SE $\frac{1}{4}$
Sec. 35-15-4W
Saline County, Kansas

4 1/2"-3436' cemented
with 75 sax

Well Commenced 6-5-51
Well Completed 6-17-51

Contractor: E. K. Carey, Contractor (Rig #1) Box 620, McPherson, Kansas
Geologist: Donald D. Hollar, with Derby Oil Co., Box 1030, Wichita, Kansas

Figures Indicate Bottom of Formation K.B.

Rotary Base & Cellar	8	Lime & Shale	2380
Shale	65	Lime & Shale	2485
Sand	73	Lime	2600
Shale & Shells	195	Lime	2685
Shale & Shells	255	Lime & Shale	2765
Sand	260	Lime & Shale	2870
Shale & Shells	310	Shale	2918
Shale & Shells	340	Lime	2965
Shale & Shells	365	Lime	3000
Lime & Shale	500	Lime	3060
Lime & Shale	725	Lime	3105
Lime & Shale	875	Lime	3145
Lime & Shale	1025	Lime	3174
Shale & Lime	1100	Lime	3208
Shale & Shells	1550	Shale & Lime	3286
Shale	1800	Shale	3300
Shale & Lime	1835	Shale & Lime	3320
Shale & Lime	1925	Shale	3394
Lime	1990	Shale	3435
Lime	2020	Lime	3437
Shale & Lime	2045		
Shale & Lime	2280		

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 - 1966
CORPORATION DIVISION
WICHITA, KANSAS

Geologist Tops:

Top Miss. 2916
Base Miss. 3208

Top Maquoketa Dolomite 3435
Total Depth 3437

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

E. K. Carey, Contractor
Herbert Rhoton
By Herbert Rhoton, Supt.

1328
2107