

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

15-167-00873-0000⁰²

API NUMBER None

COUNTY Saline

LEASE NAME Bengston WELL# 4

SPOT LOCATION w/2 w/2 NW

SEC. 36 TWP. 15 RGE. 4 (S) OR (W)

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.
TYPE OR PRINT

LEASE OPERATOR Gear Petroleum Co., Inc.

PHONE # () 316 265 3351

OPERATORS LICENSE NO. 5151

CHARACTER OF WELL oil (OIL) Gas, D&A, SWD, INPUT, WATER SUPPLY WELL

DATE WELL COMPLETED 7/12/83 PLUGGING COMMENCED 7/13/83

PLUGGING COMPLETED 7/13/83 REASON FOR ABANDONMENT OF WELL OR PRODUCING

FORMATION- Maquoketa - uneconomic

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Gilbert Toman

IS ACO-1 FILED? No IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION Maquoketa DEPTH TO TOP 3410' BOTTOM 14 T.D. 3465

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Maquoketa</u>	<u>oil</u>	<u>3410</u>	<u>14</u>	<u>15 1/2</u>	<u>103</u>	<u>None</u>
				<u>10 3/4</u>	<u>355</u>	<u>None</u>
				<u>7</u>	<u>3465</u>	<u>None</u>

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Rock bridge in 7" casing at 500', fill to surface with ready-mix, pump 75 sx pozmix in annulus between 7" and 10 3/4.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Gear Petroleum Co., Inc. LICENSE NO. 5151
ADDRESS 300 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, SS.

Jim Thatcher, Drilling & Production Manager (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT. SO HELP ME GOD.

(SIGNATURE) Jim Thatcher
(ADDRESS) 300 Sutton Place, Wichita, Ks 67202

RECEIVED
STATE CORPORATION COMMISSION
9-2-83
SEP 9 1983
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO BEFORE ME THIS 31st DAY OF August, 1983

Helen L. Coyer
NOTARY PUBLIC
Helen L. Coyer

MY COMMISSION EXPIRES: April 1, 1986

HELEN L. COYER
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 4-1-86

FORM CP-4
REVISED 06-83

15-169-008730000

ROTARY DRILLER'S LOG

Bengston Well No. 4
NW/4 Section 36-15S-4W
Saline County, Kansas

0 - 35' - Sand
35 - 245' - Shale & Shells
245 - 3362' - Lime & Shale
362 - 930' - Lime
930 - 1865' - Shale & Lime
1865 - 2070' - Lime
2070 - 2210' - Shale & Lime
2210 - 2640' - Lime
2640 - 2815' - Shale & Lime
2815 - 2900' - Shale
2900 - 3185' - Lime
3185 - 3330' - Shale
3330 - 3340' - Lime
3340 - 3415' - Shale
3415 - 3465' - Lime (TD)

NOTE: No notarized driller's log was actually received but this information compiled from E. K. Carey daily driller's log.
(Contractor)