

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15169-19078-0000
 API NUMBER

LEASE NAME Bengston

WELL NUMBER 1 SWD

SPOT LOCATION C NW

SEC. 36TWP. 15RGE. 4 (K) or (W)

COUNTY Saline

Date Well Completed 3/55

Plugging Commenced 7/24/84

Plugging Completed 7/24/84

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 300 Sutton Place, Wichita, Kansas 67202

PHONE # (316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well SWD & Water supply
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? - - If not, is well log attached? yes

Producing formation - - Depth to top - - bottom - - T.D. 277

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Sand	Water	249	280	10 3/4	120	None
				7	249	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set Run tubing to 280' - circulate 50 sx 50/50 poz cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum Co., Inc./Allied Cementing License No.
 Address Allied - Box 31
Russell, KS


RECEIVED
 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgewick, ss.

Jim Thatcher, Drilling & Production Mgr (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Thatcher

(Address) 300 Sutton Place, Wichita, KS



SUBSCRIBED AND SWORN TO before me this 24th day of September, 1984

Helen L. Coyer
 Notary Public

My Commission expires: April 1, 1986

15-169-19078-0000

Sec 36-15S-4W

Docket #
C-4311

WELL LOG

REPUBLIC NATURAL GAS COMPANY
Bengtson SWD #1
Approx. C NW/4 Sec. 36-15-4W
Smolan Pool, Saline Co., Kansas
TD 277', Comm. 1-10-55, Comp. 1-16-55

Figures indicate bottom of formation.

Soil	5'
Clay and Shale	20'
Sand	35'
Shale and Shells	245'
Shale	250'
Sand	277' T.D.

10-3/4" O.D. surface casing set at 120' and cemented with 100 sacks--cement circulated to surface. 7" O.D. casing set at 249' and cemented with 100 sacks. Input test indicated well was taking water at a rate of 135 B/Hr. Cement circulated to surface around 7" casing. Completed for Salt Water Disposal

SIGNED

[Signature]
District Engineer

Subscribed and sworn to before me this 28th day of March, 1955

My Commission Expires - 8-20-55

[Signature]
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1984

CONSERVATION DIVISION
Wichita, Kansas