

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Saline County, Sec. 36 Twp. 15 Rge. 4 W (E) (W)

Location as "NE/CNWxSWx" or footage from lines SW SW NW

Lease Owner Arvel Smith

Lease Name Bengatan Well No. 2

Office Address Rt. 1 Towanda, Kansas 67144

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 9-5 19 51

Application for plugging filed 6-10- 19 72

Application for plugging approved 6-11 19 72

Plugging commenced 7-3 19 72

Plugging completed 7-10 19 72

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toran

Producing formation Depth to top Bottom Total Depth of Well 3418' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2947'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3408' to 3400'. Dumped 5 ax of cement. Mudded hole to 215'. Made 10' of rock bridge. Dumped 3 Yrds. of Ready-Mix cement, filling to the bottom of the collar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 14 1972  
7-14-72  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]

2809 King St. Hutchinson, Kansas 67501

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 72

My commission expires January 5, 1974



[Signature] Notary Public.

**STENCILED**

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
502 East Murdock,  
Wichita, Kansas

**ORIGINAL**

OCT 27 1951


15-169-00869-0000

Company- E. K. CAREY  
Farm- Bengston No. 2

SEC. 36 T. 15 R. 1W  
SW SW NW

Total Depth. 3418 K.B.  
Comm. 8-24-51 Comp. 9-5-51  
Shot or Treated.  
Contractor. E.K. Carey  
Issued. 10-27-51

County Saline  
KANSAS



CASING:  
8 5/8" 324' cem. w/225 SX.  
5 1/2" 3416.5' cem w/75 SK.

Elevation. 1307 K.B.

Production. DD 1256 bbls

Figures Indicate Bottom of Formations. K.B.

rotary base & cellar	7
shale	35
sand	40
shale, shells	240
sand, shale	260
lime, shale	324
lime	445
lime, shale	1065
shale, shells	1405
shale, lime	2258
lime	2610
shale	2695
shale, shells	2770
shale, lime	2893
lime	3195
shale	3334
lime	3346
shale	3416
lime	3418
Total Depth	

Tops:	
Mississippi Lime	2892
Kinderhook Shale	3192
Hunton	3340
Maquoketa Shale	3350
Mauoketa Dolomite	3416

Set 5 1/2" casing @ 3416 1/2'  
(1 1/2' off bottom)

8 5/8" x 5 1/2" Head  
7' below K.B.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 12 1972  
CONSERVATION DIVISION  
Wichita, Kansas