

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Saline County, Sec. 36 Twp. 15 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Fender Pipe & Supply, Inc.
Lease Name Burk Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5-20-66 _____ 19____
Plugging completed 5-23-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3438 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	323'	None
				4-1/2"	3434'	3035'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3438', sanded hole to 3425' and dumped 3 sacks of cement @ 3425' with dump bailer. Pulled 4 1/2" casing, set rock bridge from 260' to 250' and dumped 20 sacks of cement. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

MAY 31 1966
5-31-66

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1966

Milton J. Volin
Notary Public.

My commission expires

May 20, 1968

ROTARY DRILLER'S LOG

15.169.00503.0000

Derby Oil Co., Operator
Box 1030
Wichita, Kansas

Elevation
1329 K.B.

Burk #1

Casing Record:

C-SW₁-SW₄-SW₈
Sec. 53-15S-4W
Saline County, Kansas

8 5/8" 320' cemented
with 250 sax

6 1/2" 3434' cemented
with 70 sax

Well Commenced 5-20-51
Well Completed 3-5-51

Contractor: E. K. Carey, Contractor, (Rig #1) Box 620, McPherson, Kansas
Geologist: Elble McNeill, with Derby Oil Co., Box 1030, Wichita, Kansas

Figures Indicate Bottom of Formations K.B.

Rotary Base & Celler	8	Shale	2280
Shale & Shells	70	Lime	2325
Sand	85	Lime & Shale	2425
Shale	205	Lime & Shale	2540
Shale & Shells	250	Lime	2590
Sand	260	Sand & Lime	2570
Shale & Shells	320	Lime	2615
Shale & Shells	410	Lime	2690
Lime	500	Lime	2735
Shale & Lime	530	Lime & Shale	2805
Salt	530	Lime & Shale	2910
Lime & Shale	745	Shale	2915
Shale & Lime	975	Lime Misc	2964
Shale & Shells	1445	Lime	3016
Shale & Lime	1710	Lime & Chat	3070
Lime	1725	Lime	3120
Lime & Shale	1845	Lime	3160
Lime & Shale	1985	Lime	3196
Lime	2003	Lime	3240
Sand	2015	Shale	3296
Shale	2070	Lime & Shale	3368
Shale & Lime	2230	Shale	3420
		Shale	3433
		Lime	3438

W.A.Y. 6-1966
Geologist, McPherson, Kansas

Geologist Tops:

Top Wiss. 2910 (-1531)
Kingertook 3204
Hunton 3356

Maquoketa Shale 3368
Maquoketa Dolomite 3433 (-2104)

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

E. K. CAREY, CONTRACTOR

H. Rhoton

By Herbert Rhoton, Supt.