


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Saline County. Sec. 36 Twp. 15 Rge. 4 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines SE NE SW

Lease Owner Fender Pipe & Supply, Inc.

Lease Name Burk Well No. 2

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 8-5-66 19

Plugging completed 8-11-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3433 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	333'	None
				4-1/2"	3432'	2992'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 3410', and dumped 3 sacks of cement with dump bailer. Pulled 4 1/2" casing, set 10' rock bridge @ 250' and dumped 20 sacks of cement. Mudded hole to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 26 1966  
8-26-66  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (INDEX OR REGISTER) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 1966



My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

## ROTARY DRILLER'S LOG

Derby Oil Co., Operator  
Box 1030  
Wichita, Kansas

Elevation  
1315 K. B.

Burk #2

Top 8-5/8" x 4 1/2" Head 6.80  
below K. B.

C - SE-NE of SW  
Sec. 36-15S-4W  
Saline County, Kansas

Casing Record:

8-5/8" 330' cemented  
250 sx  
4 1/2" 3431.50 cemented  
75 sx

Well Commenced: 6-15-51  
Well Completed: 7- 2-51

Contractor: E. K. Carey, Contractor, (Rig #1) Box 620, McPherson, Kansas  
Geologist: Don Holler, with Derby Oil Company, Box 1030, Wichita, Kansas

Figures Indicate Bottom of Formations K. B.

Rotary Base & Cellar	8	Shale & Lime	2300
Clay & Shale	28	Lime & Shale	2410
Sand	36	Lime & Shale	2470
Shale & Shells	90	Lime	2560
Shale & Shells	320	Lime	2635
Lime & Shells	330	Lime	2690
Shale & Shells	360	Lime & Shale	2715
Lime	470	Lime & Shale Streaks	2765
Lime & Shale	530	Shale	2860
Salt	570	Shale	2893
Lime & Shale	700	Lime	2930
Shale & Lime	795	Lime	2961
Lime & Shale	1005	Lime	2996
Shale & Shells	1405	Lime	3038
Shale & Lime Shells	1615	Lime	3094
Lime & Shale	1765	Lime	3113
Lime & Shale	1895	Lime	3174
Lime & Shale	1910	Lime	3190
Lime	1985	Shale & Lime	3236
Lime	2095	Shale	3312
Lime & Shale	2110	Shale	3340
Shale & Lime	2185	Lime & Shale	3366
		Lime & Shale	3409
		Shale & Lime	3433

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

E. K. CAREY, CONTRACTOR

By Herbert Rhoton, Supt.

*Herbert Rhoton*