

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Saline County, Sec. 36 Twp. 15 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner Fender Pipe & Supply, Inc.

Lease Name Burk Well No. 6

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 5-24-66 19

Plugging completed 5-26-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3429 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	321'	None
				5-1/2"	3427'	2878'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3429', sanded hole to 3400' and dumped 5 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2 casing, set rock bridge from 260' to 250' and dumped 20 sacks of cement. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 1 1966

6-1-66

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 1966

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

15169-00508-0000

WELL LOG

THE DERBY OIL COMPANY
Burk #6

SE SE NW ^{FFW}
Section 36-15S-4W
Saline County, Kansas

Total Depth: 3429'
Commenced: August 17, 1952
Completed: September 2, 1952
Contractor: Shields Drilling Co., Inc.

RECEIVED
OIL & GAS CORPORATION COMMISSION
MAY 6 - 1966
CONSERVATION DIVISION
Wichita, Kansas

CASING RECORD

Size	Run	Pulled
8 5/8"	340'	Cmtd. w/ 590 sax
5 1/2"	3427'	Cmtd. w/ 75 sax

Elevation: 1319

----- -Figures Indicate Bottom of Formation - -----

Surface clay & shale	70	Shale & Lime	2237
Shale	120	Lime & Shale	2765
Shale & Shells	215	Lime	2845
Shale & Gyp	311	Lime & Shale	2986
Anhydrite	340	Lime	3020
Cemented 11 jts. of 8 5/8"		Shale & Lime	3054
new surface pipe w/ 590 sax		Lime & Shale	3085
Lime	400	Lime	3146
Broken Anhydrite	435	Lime & Shale	3225
Lime & Shale	935	Shale	3358
Shale & Lime	1080	Lime & Shale	3410
Lime, Shale & Salt	1190	Shale & Lime	3429 T.D.
Shale, Shells & Salt	1450	Cemented 5 1/2" casing	
Shale & Lime Streaks	1710	@ 3427' w/ 75 sax.	
Shale	1760		
Shale & Lime	1785		
Lime & Shale	2165		

TOPS

Maquoketa Dolomite	3427'
Rotary Total Depth	3429'