

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Saline County, Sec. 36 Twp. 15 Rge. 4 (E) W (W)

Location as "NE/CNW/SE/SW" or footage from lines NE SE SW

Lease Owner Fender Pipe & Supply, Inc.

Lease Name Burk Well No. 7

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 5-27-66 19

Plugging completed 5-31-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3429 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	343'	None
				5-1/2"	3427'	2852'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3429', sanded hole to 3415' and dumped 5 sacks of cement @ 3415' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 250' to 240' and dumped 20 sacks of cement. Mudded hole to 30' and capped well with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN - 8 1966  
6-6-66  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of June, 1966

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

WELL LOG

15.169.00509.0000

DERBY OIL CO.  
Burk #7

NE SE SW  
Sec. 36, Twp. 15, Rge. 4  
Saline County, Kansas

Total Depth: 3427'  
Commenced: November 20, 1952  
Completed: December 3, 1952  
Drilled by Shields Drilling Co., Inc.

CASING RECORD

Size	Run	Cemented
8 5/8"	⊙ 339'	Cmtd. w/ 250 Sax
5 1/2"	⊙ 3426'	Cmtd. w/ 75 Sax

Elevation: 1319' RB  
Treatment:  
Production:

-----Figures Indicate Bottom of Formation-----

Surface & Sand	107	Lime & Shale	2450
Shale	290	Lime	2470
Shale & Gyp	330	Lime & Shale	2780
Lime	339	Shale & Lime	2930
Lime Bkn.	440	Lime & Shale	2980
Lime & Shale	500	Shale & Lime	3015
Shale & Lime	750	Lime & Shale	3075
Lime & Shale	1020	Lime	3129
Shale	1200	Shale	3155
Salt	1240	Lime & Shale	3200
Lime & Shale	1370	Shale	3425
Lime, Shale & Salt	1465	Dolomite	3427 TD

TOPS

Maquoketa Dolomite 3425'

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 - 1966  
CONSERVATION DIVISION  
Wichita, Kansas