

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5030
Name: Vess Oil Corporation
Address 1: 1700 Waterfront Parkway, Building 500
Address 2: _____
City: Wichita State: KS Zip: 67206 + 6619
Contact Person: Casey Coats
Phone: (316) 682-1537 Ext. 104
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

API No. 15 - 097-20639-00-01
Spot Description: SW SE
_____ Sec. 26 Twp. 30 S. R. 18 East West
660 Feet from North / South Line of Section
1,980 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kiowa
Lease Name: Yost Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

Plugging Commenced: 9-2-11
Plugging Completed: 9-8-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	536	None
			5-1/2"	5036	2500'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 4843' and 5 sacks cement. Cut casing loose @2500', pulled up to 1820', well kicked off, pumped plug @1820' with 40 sxs. cement, pulled up to 1120', pumped 15 sxs. gel and 50 sxs. cement, , pulled up to 560', pumped 50 sxs. cement, pulled up to 40' and pumped 40 sxs. cement, Plugging Complete

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.
Address 1: P.O. Box 467 Address 2: _____
City: Chase State: Kansas Zip: 67524 + 0467
Phone: (620) 938-2943
Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Rice, ss.
Mike Kelso Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEP 22 2011

KCC WICHITA