

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31280
Name: Birk Petroleum
Address 1: 874 12th Rd SW
Address 2: _____
City: Burlington State: Ks Zip: 66839 + _____
Contact Person: Brian I Birk
Phone: (620) 364-1311
Type of Well: (Check one) ☐ Oil Well ☐ Gas Well ☐ OG ☒ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Squirrel - Dry Depth to Top: 1021 Bottom: 1037 T.D. 1037
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 031-23021-00-00
Spot Description: _____
NE SE NE SW Sec. 15 Twp. 22 S. R. 16 ☒ East ☐ West
1,815 Feet from ☐ North / ☒ South Line of Section
2,805 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☒ SE ☐ SW
County: Coffey
Lease Name: Raymond Klaus Well #: 42
Date Well Completed: 09/12/2011
The plugging proposal was approved on: 09/12/2011 (Date)
by: Troy (KCC District Agent's Name)
Plugging Commenced: 09/12/2011
Plugging Completed: 09/12/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Surface	water	Surface	7"	40'	
Kansas City	Water				
Squirrel	Dry				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Connect to drill pipe. Set 50' plug at TD using 15 sx cement. Mix and pump 2 sx gel. Pull out to base of KC at 650'. Set 50' plug at base of KC using 15 sx cement. Mix and pump 2 sx gel. Pull out to 250' depth. Set solid plug 250' to surface using 60 sx cement.

RECEIVED

SEP 19 2011

Plugging Contractor License #: 31280 Name: Birk Petroleum **KCC WICHITA**
Address 1: 874 12th Rd SW Address 2: _____
City: Burlington State: Ks Zip: 66839 + _____
Phone: (620) 364-1311
Name of Party Responsible for Plugging Fees: Birk Petroleum
State of Kansas County: Coffey, ss.
Laura C Birk ☒ Employee of Operator or ☐ Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

Signature: Laura C Birk