

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

24

OPERATOR: License #: 4058  
Name: American Warrior Inc  
Address 1: PO Box 399  
Address 2: \_\_\_\_\_  
City: Garden City State: KS Zip: 67846 + \_\_\_\_\_  
Contact Person: Kevin Wiles SR  
Phone: (620) 275-2963 Ext. 306  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 009-25 920-0000  
Spot Description: SE Sec. 19-20s-12w  
NW  NE  SW  SE Sec. 19 Twp. 20 S. R. 12  East  West  
1,170 Feet from  North /  South Line of Section  
1,840 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Haddon-Fischer Well #: 1-19  
Date Well Completed: 4/3/06  
The plugging proposal was approved on: 9/1/11 (Date)  
by: Case Morris (KCC District Agent's Name)  
Plugging Commenced: 9/6/11  
Plugging Completed: 9/7/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	312'	200 Sacks Cement
		Production	5 1/2"	3599'	150 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole sand at 3240'; bailed 5 sacks cement on sand. Cut surface casing off 4' below ground. Ripped casing at 2130' & 1950'. Pulled to 1550' & pumped 125 sacks cement, 3% cc & 300# hulls. Pulled to 700' & pumped 40 sacks cement, 3% cc & 100# hulls. Pulled to 315' & pumped 40 sacks cement, 3% cc & 100# hulls. Pulled to 150' & circulated with 55 sacks cement.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc  
Address 1: 190 US Hwy 56 Address 2: \_\_\_\_\_  
City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_  
Phone: (620) 727-3409  
Name of Party Responsible for Plugging Fees: American Warrior, Inc.  
State of KANSAS County, Finney, ss.  
Kevin Wiles SR  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: \_\_\_\_\_

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

SEP 16 2011

KCC WICHITA