

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20506-00-00
Spot: NESENE Sec/Twnshp/Rge: 9-13S-21W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: KELLER A Well #: 2
County: TREGO Total Vertical Depth: 3896 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3200		
CIBP		3961		
SURF	8.625	260	0	175 SX
PROD	4.5	3886	0	275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/03/2011 10:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: ALAN Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.
CIBP 3961'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/03/2011 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3800' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 2800' - pumped 100 sxs cement.
Pulled tubing to 1300' - pumped 75 sxs cement - good circulation of cement.
Pulled tubing out - tied onto backside - squeezed with no cement.
S.I.P. 300#. Full.
Topped off 4 1/2" casing with 10 sxs cement - full - done.

Perfs:


Top	Bot	Thru	Comments
3876	3880		
3654	3661		
3631	3637		
3509	3516		
3458	3462		
3442	3444		
3266	3270		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN) RECEIVED

CM

JUN 17 2011

Form CP-2/3

KCC WICHITA

JUN 06 2011