

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-21197-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 17-29S-41W
2307 feet from N Section Line, 2292 feet from E Section Line
Lease Name: WARD Well #: 1-17
County: STANTON Total Vertical Depth: 5532 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1637		WITH 600 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/14/2011 7:15 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: ALAN LOFTIS Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 80 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: NONE
Date/Time Plugging Completed: 06/14/2011 9:15 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

Perfs:

1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 80 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: DP

District: 01

Signed

Jerry W. Stapleton
(TECHNICIAN)
PIRT II

RECEIVED
JUN 16 2011
KCC DODGE CITY

RECEIVED
JUN 17 2011
KCC WICHITA

FORM CP-373