

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21474-00-01  
Spot: NESESW Sec/Twnshp/Rge: 32-31S-17W  
990 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: YORK B Well #: 1  
County: COMANCHE Total Vertical Depth: 5715 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5070		WITH 2 SX CMT
CIBP		5146		
SURF	10.75	253		WITH 250 SX CMT
COND	20	77		
PROD	4.5	5714	1400	WITH 220 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2011 11:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: CARL W. DURR Company: WOOLSEY OPERATING Phone: (620) 886-5606

Proposed Plugging Method: CIBP @ 5070' WITH 2 SX CMT. PLUG AT 1100' WITH 12 SX GEL & 50 SX CMT. PLUG AT 300' WITH 70 SX CMT. PLUG AT 60' WITH 25 SX CMT. CHECK 10 3/4" X 20" ANNULUS WITH 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/08/2011 2:05 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5070' WITH 2 SX CMT. 1ST PLUG AT 1100' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 70 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT. CMT CIRCULATED. BACKSIDE WAS FULL.

Perfs:

Top	Bot	Thru	Comments
5465	5483		
5148	5160		
5121	5144		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
JUN 15 2011  
KCC DODGE CITY

Signed

*Eric MacLaren*  
(TECHNICIAN)

RECEIVED  
JUN 22 2011  
KCC WICHITA

Form CP-275