

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-03771-00-02  
Spot: SWNENE Sec/Twnshp/Rge: 11-15S-14W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: FLEGLER C Well #: 6  
County: RUSSELL Total Vertical Depth: 3355 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	10.75	868	0	875 SX
PROD	5.5	3335	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2011 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TIM SCHECK Company: SCHECK OIL OPERATION Phone: (785) 483-4096

Proposed  
Plugging  
Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Ordered 50 sxs 60/40 pozmix - 4% gel.  
Perf: 860' - 1450'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/22/2011 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2820' - pumped 75 sxs cement with 100# hulls.  
Pulled tubing to 2063' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1058' - pumped 165 sxs cement - cement circulated.  
Fluids also started to circulate out of Braden head.  
POOH. Hooked up to casing - pumped 125 sxs cement - had good circulation - both sides went on a vacuum.  
WOC for two hours. Pumped 40 sxs cement down casing - shut down - stayed full.  
Ordered more cement - pumped 15 sxs down Braden head at P.S.I. 150#.  
Cement started to circulate in cellar. Shut in both sides.

Remarks: QUALITY OIL WELL CEMENTING-TICKET #4666.

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

RECEIVED

CM

JUN 27 2011

Form CP-2/3

KCC WICHITA

JUN 23 2011