

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23016-00-00  
Spot: E2NENWNE Sec/Twnshp/Rge: 18-11S-18W  
330 feet from N Section Line, 1566 feet from E Section Line  
Lease Name: FRISBIE B Well #: 2  
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	330	0	175 SX
PROD	5.5	3599	0	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2011 8:45 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Revd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Packer stuck in the hole at 2836'. Top of tubing 2640'.  
Squeezed 800' w/350 sxs.  
Emergency plug with rig over the hole.  
Lease worked up by Pat Staab.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/23/2011 11:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 1850' and 1250'.  
Express Well Service RIH with tubing to 2640'.  
Quality Oil Well Cementing rigged to tubing and pumped 75 sxs neat - followed with 75 sxs cement with 200# hulls mixed in.  
Pulled tubing to 1250'. Quality rigged to tubing and pumped 130 sxs cement with 200# hulls to circulate cement to surface.  
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 15 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.  
8 5/8" was full of cement from squeezing at 800' with 350 sxs cement.

Perfs:


Top	Bot	Thru	Comments
3163	3397		
3066	3163		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4667.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

RECEIVED

JUN 27 2011

Form CP-2/3

JUN 23 2011

KCC WICHITA