

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21198-00-00
Spot: NWSESWNW Sec/Twnshp/Rge: 21-35S-43W
477 feet from S Section Line, 4573 feet from E Section Line
Lease Name: BOALDIN Well #: 1-21
County: MORTON Total Vertical Depth: 4728 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4410		WITH 2 SX CMT
SURF	8.625	1379		WITH 375 SX CMT
PROD	5.5	4728	1431	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/16/2011 12:30 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (582) 254-1881

Proposed Plugging Method: CIBP @ 4410' WITH 2 SX CMT. PLUG AT 1400' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/17/2011 3:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 4410' WITH 2 SX CMT. 1ST PLUG AT 1415' WITH 50 SX CMT. GOOD CIRCULATION FOR FIRST HALF OF DISPLACEMENT. LOST CIRCULATION DURING LAST HALF OF DISPLACEMENT. POOH W/400' CASING & SHUT DOWN 1 HOUR TO TAG TOC. RIH W/WIRELINE TO 1500' WITHOUT TAGGING CMT. FLUID LEVEL AT 530'. SDON. 6/17/11: TAGGED TOC @ 2067'. RIH WITH CASING TO 1415'. CIRCULATED HOLE WITH MUD. CIRCULATED & HELD OK. PLUG AT 1415' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4556	4568		KEYES

RECEIVED
JUN 30 2011
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLasky
(TECHNICIAN)

RECEIVED

JUN 20 2011

KCC DODGE CITY

Form CP 2/3