

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-21013-00-00
Spot: W2NWNENE Sec/Twnshp/Rge: 34-14S-33W
330 feet from N Section Line, 1090 feet from E Section Line
Lease Name: KNOPP Well #: 1
County: LOGAN Total Vertical Depth: 4728 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/28/2011 12:00 AM
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.
Proposal Rcvd. from: RICK Company: RAYMOND OIL COMPANY, INC. Phone: (316) 267-4214

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 06/28/2011 9:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfs:

1st. Plug at 2310' w/25 sxs.
2nd. Plug at 1175' w/100 sxs.
3rd. Plug at 320' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

RECEIVED
JUL 01 2011
KCC WICHITA

Remarks: CONSOLIDATED ACID AND CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce D. Basye
(TECHNICIAN)

cm

Form CP-2/3

JUN 29 2011