

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20599-00-02
Spot: N2NE Sec/Twnshp/Rge: 14-30S-26W
661 feet from N Section Line, 1521 feet from E Section Line
Lease Name: WRIGHT OWWO Well #: 1
County: MEADE Total Vertical Depth: 5500 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1525		WITH 750 SX CMT
COND	16	59		
PROD	4.5	3813	0	WITH 135 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/23/2011 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/27/2011 11:50 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

6/23/11: 1ST PLUG PUMPED 300# HULLS & 30 SX CMT. DISPLACED TO 3300'. 2ND PLUG PERFORATED 4 1/2" CASING AT 1550'. PUMP 150 SX CMT THROUGH TBG @ 1516'. NO CIRCULATION OF CMT. WELL PRESSURED TO 850'. SDON. 3RD PLUG RAN TEMPERATURE SURVEY. TOC @ 1390'. PERFORATED AT 1350'. SDFWE.
6/27/11: 4TH PLUG TIHWT TO 1345'. ESTABLISH RATE. PUMPED 155 SX CMT. CIRCULATED CMT TO SURFACE. 5TH PLUG CIRCULATED INSIDE 4 1/2" CASING WITH 75 SX CMT. POHWT. FILL CASING WITH 10 SX CMT. FILL ANNULUS WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3610	3616		
3599	3609		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

RECEIVED
JUL 08 2011

KCC WICHITA

District: 01

Signed Steve Durrant

(TECHNICIAN)

RECEIVED

JUN 30 2011

KCC DODGE CITY