

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20059-00-02
Spot: W2NESW Sec/Twnshp/Rge: 35-32S-31W
1980 feet from S Section Line, 1680 feet from W Section Line
Lease Name: GANO A Well #: 3
County: SEWARD Total Vertical Depth: 6056 feet

Operator License No.: 33709
Op Name: POGO PRODUCING COMPANY LLC
Address: 717 TEXAS, STE 2100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4640		WITH 2 SX CMT
CIBP		5000		
SURF	8.625	1610		WITH 800 SX CMT
PROD	4.5	6055	1651	WITH 340 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/21/2011 10:00 AM
Plug Co. License No.: 34572 Plug Co. Name: HOLMAN WELL SERVICE, LLC
Proposal Rcvd. from: FRED MUNIER Company: POGO PRODUCING Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2011 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

****CASING LEAK 2929-2944**** CIBP @ 4640' WITH 2 SX CMT. (COULD NOT GET THROUGH FILL-UP AT 4640'.) LOAD 4 1/2" CASING WITH MUD. SHOOT OFF CASING AT 1651'. TOOH W/ 4 1/2" CASING. RUN 2 3/8" TBG TO 1650'. CIRCULATE HOLE WITH MUD. 1ST PLUG AT 1650' WITH 125 SX CMT. 2ND PLUG AT 620' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5965	5969		
5942	5947		
5890	5896		
4900	4904		
4864	4871		

RECEIVED
JUL 08 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR** USED CLASS H CEMENT BY HOLMAN SERVICES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
JUN 30 2011
KCC DODGE CITY

Form CP-213