

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25243-00-00
Spot: SESWNWSW Sec/Twnshp/Rge: 35-16S-24W
1327 feet from S Section Line, 390 feet from W Section Line
Lease Name: ALLEN Well #: 1
County: NESS Total Vertical Depth: 4570 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 236 | | WITH 150 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/06/2011 2:00 AM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Rcvd. from: TERI Company: MAVERICK DRILLING LLC Phone: (316) 262-6700

Proposed Plugging Method: 1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 06/06/2011 4:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

1ST PLUG AT 1895' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: DP

RECEIVED
JUL 08 2011
KCC WICHITA

District: 01

RECEIVED
JUN 30 2011
KCC DODGE CITY

Signed Steve Durrant
(TECHNICIAN)