

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25368-00-00  
Spot: NESWNESE Sec/Twnshp/Rge: 5-18S-11W  
1700 feet from S Section Line, 900 feet from E Section Line  
Lease Name: STUEDER Well #: 1-5  
County: BARTON Total Vertical Depth: 3475 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	347	0	275 sx
T1	2.875	3430		
PROD	5.5	3446	1972	25/150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/01/2011 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: KURT STRUBE Company: SAMUEL GARY JR. & ASSOCIATES Phone: (303) 831-4673

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Casing pulled at 1972' - leaving 1474' of 5 1/2" casing in the well.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/01/2011 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Pulled casing to 1369' - pumped 160 sxs cement with 300# hulls.  
Pulled casing to 622' - pumped 25 sxs cement.  
Pulled casing to 402' - pumped 100 sxs cement - cement circulated.  
POOH. Topped off hole with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3056	3061		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4893.

Plugged through: CSG

District: 04

Signed

*RAD.kd*

(TECHNICIAN)

CM

RECEIVED  
JUL 08 2011  
KCC WICHITA

Form CP-2/3

JUL 05 2011